



Ventura County Community College District

PURCHASING DEPARTMENT

DATE: January 10, 2020
TO: All Bidders
FROM: Jo Nell Miller, Purchasing Specialist
SUBJECT: Addendum 1 – **Bid 590 Moorpark College Stadium Lighting Project**

This addendum is hereby made part of the Contract Documents to the same extent as though it was originally included therein and takes precedence over the original documents. The outdated pages must be replaced with any updated and/or changed pages when submitting your bid. Acknowledge receipt of all addenda on the Bid Form.

The bid opening remains on **Tuesday, January 28, 2020**. Bids must be received no later than **3:00 p.m.** at 761 E Daily Drive, Suite 200, Camarillo, CA 93010. Properly mark the outside of the exterior envelope on your submitted bid with the Bid Number and Name according to the requirements stated in the bid packet directions.

If you choose not to participate in this particular bid, please sign the Bid Proposal stating “no bid” and email it back to me at jonellmiller@vcccd.edu.

It is the responsibility of the Bidder to verify that their proposal has been received by the VCCCD Purchasing Department prior to the opening date. Verification of receipt can be made through the listed Purchasing Specialist.

The deadline for questions is Friday, January 17, 2020.

The attached information is in answer to questions asked at the job walk.

End of Section

Date: January 10, 2020

To: JoNell Miller, VCCCD
Purchasing Department

From: Kenneth Lucci, P.E. 

Subject: Moorpark College Football Field Lighting - Contractor site walk on 1-9-2020

The following items were discussed during our site walk held at the Football Field:

- Voltage at each of the panelboards to be replaced (at the bottom area of each pole) is 120/208 vac with the amperage as noted on the CD (contract documents) single line. All breakers will be new and match the CDs. Breakers will be bolt on type.
- Power to the panels is fed from the M & O area.
- Contractor to remove and properly dispose of the old MH fixtures.
- Contractor to focus each fixture based on a plan to be provided by the EOR.
- Lighting fixtures are per CDs with wireless control
- Two wireless hubs are to be provided, one at the north west pole base and one in the enclosed booth. Each hub requires 120 vac by contractor.
- Lighting fixtures to be mounted on the existing crossarms
- Existing cage on each pole shall be contractor removed.
- Track is to be protected from wheel damage from crane or boom truck. Any cost for repair of damage to track will be borne by the contractor.
- Contractor to provide for his own restroom facilities
- Contractor to schedule all work with the M & O director
- All RFIs and questions shall be in writing and sent to JoNell Miller of VCCCD.
- Fixtures shall have stainless steel safety cables on fixtures to crossarms.
- Contractor is responsible for programming of the fixtures per the owner's requirements