



Ventura County Community College District

PURCHASING DEPARTMENT

DATE: July 14, 2021
TO: All Bidders
FROM: Jo Nell Miller, Purchasing Specialist
SUBJECT: Addendum 1 Revised – Bid 622 Moorpark College Softball Backstop and Fencing Project

This addendum is hereby made part of the Contract Documents to the same extent as though it was originally included therein and takes precedence over the original documents. The outdated pages must be replaced with any updated and/or changed pages when submitting your bid. Acknowledge receipt of all addenda on the Bid Form.

The bid opening remains on **Wednesday, July 21, 2021**. Bids must be received no later than **3:00 p.m.** at 761 E Daily Drive, Suite 200, Camarillo, CA 93010. Properly mark the outside of the exterior envelope on your submitted bid with the Bid Number and Name according to the requirements stated in the bid packet directions.

It is the responsibility of the Bidder to verify that their proposal has been received by the VCCCD Purchasing Department prior to the opening date. Verification of receipt can be made through the listed Purchasing Specialist.

Attached is the **Technical Specs 061721_020-MPC-033**.

The following information is in answer to questions that were asked at the job walk and via email request. The deadline for questions was **Tuesday, July 13, 2021, at 3:00 p.m.** No further questions will be accepted.

1. The work will be awarded to only one contractor.
2. Pump Concrete can be done from road in front of tennis courts.
3. Moorpark College will work with the successful contractor to provide adequate access, laydown and parking.
4. Concrete walkway demo is specified in the plans.
5. Vegetation is to be removed where grading is required. No new landscape included.
6. There is waterproofing and drainage behind retaining wall included.
7. The retaining wall is limited to 2'-4" maximum but wall continues to 8' for future use as dugout rear wall.
8. The North end Point of Connection for irrigation line is just on the other side of the Baseball fencing on the baseball warning track. Backfill and restore track after connection. College can provide crushed brick material as needed.
9. The existing low CMU curb behind third base dugout is to be removed.
10. The sizes of the two irrigation valves are in Section 32_80000. The size if the irrigation control valves is 2".



Ventura County Community College District

PURCHASING DEPARTMENT

End of Section