

## Exhibit A

RE: BID 659, VENTURA COLLEGE: M BUILDING  
AT  
VENTURA COLLEGE

FROM: OWNER: VENTURA COUNTY COMMUNITY COLLEGE DISTRICT  
PURCHASING DEPARTMENT  
761 E DAILY DRIVE, SUITE 200  
CAMARILLO, CA, 93010


TO: ALL PROSPECTIVE BIDDERS:

The Exhibit consists of (21) pages and (02) marked up drawings:

- A. CHANGES TO BIDDING DOCUMENTS: Reference documents shown on this Exhibit is to be captured as part of the contractor's as-builts through shop drawings.
- B. CHANGES TO SPECIFICATIONS: None.
- C. CHANGES TO DRAWINGS: Noted in these reference documents are markups on sheets A-201 and A-202 noting existing conditions and proposed final floor plan layout. Reference documents shown on this Exhibit are to be captured as part of the contractor's as-builts through shop drawings.
- D. OTHER CHANGES AS SET FORTH: None

Exhibit A

# FOR REFERENCE ONLY



**1** INTERIOR DEMO PLAN - BUILDING C  
SCALE: 1/4" = 1'-0"

## DEMO PLAN NOTES

- A. PATCH WALL AND SLAB AS REQUIRED WHERE DEMOLITION OCCURS. PREPARE SURFACES TO RECEIVE NEW FINISHES.
- B. REMOVE ALL EXISTING BLANK COVER PLATES. PATCH ALL UNUSED OUTLET HOLES AND PREP WALLS FOR NEW FINISH.
- C. IN PARTITIONS BEING DEMOLISHED: REMOVE ALL ASSOCIATED POWER, TELE/DATA LINES, CABLING, ELECTRICAL SWITCHING, THERMOSTATS, AND CONDUITS. SAFE-OFF POWER BACK TO SOURCE.
- D. REMOVE ALL UNSECURED CABLING THROUGHOUT DEMOLITION AREAS. SECURE ALL REMAINING CABLING AS REQUIRED TO MEET CURRENT CODES.
- E. REMOVE ALL HILTI SHOT PINS FROM FLOOR SLAB. PATCH AND REPAIR AS REQUIRED.
- F. FOR ADDITIONAL GENERAL NOTES, LEGENDS, AND SCHEDULES, REFER TO SHEETS A-001 THROUGH A-006
- G. AREAS NOT MARKED OR HIGHLIGHTED OR CALLED OUT PER LEGEND ARE NOT IN CONTRACT ON THIS SHEET, TYPICAL.
- H. GC TO PROVIDE DUST PROTECTION THROUGHOUT DEMOLITION AND CONSTRUCTION.
- I. ARCHITECT HAS CONDUCTED NO TEST FOR, AND MADE NO DETERMINATION OF, THE PRESENCE OR LACK OF ASBESTOS OR OTHER HAZARDOUS OR TOXIC SUBSTANCES.
- J. ALL WORK SHOWN REFLECTS AS-BUILT MEASUREMENTS. HOWEVER, ANY NEW MODIFICATIONS TO THE SUITE SHALL REQUIRE FIELD VERIFICATION OF ALL DIMENSIONS SHOWN ON THIS PLAN PRIOR TO COMMENCING WORK.
- K. REFER TO MECHANICAL, ELECTRICAL, MECHANICAL, AND PLUMBING SHEETS FOR ADDITIONAL DEMOLITION INFORMATION.

## DEMO KEY NOTES

- 01 REMOVE ALL 3/8" PLYWOOD FROM INTERIOR WALLS TO EXPOSE STUDS AS INDICATED WITH DASHED LINES. (3/8" PLYWOOD LOCATED AT ALL (E) WDW'S SILL-JAMB-HEAD TO REMAIN)
- 02 SAWCUT EXISTING SLAB TO PREPARE FOR NEW SLAB AND DRAIN IN NEW SHOWER(S). SEE FLOOR PLAN FOR ADDITIONAL INFORMATION A-202
- 03 REMOVE (E) CONTROL BOX & CONDUIT FOR LAN GATE ROUTER & EXHAUST FANS - RELOCATE PER ELECTRICAL PLANS - SEE DETAIL SECTION B2/A801. REFER TO ELECTRICAL PLANS PRIOR TO REMOVAL.
- 04 ELECTRICAL SUB PANEL BOXES TO REMAIN - SEE ELECTRICAL PLANS FOR ADDITIONAL INFORMATION
- 05 EXISTING LAN (NETWORK) CONDUIT TO REMAIN - SEE ELECTRICAL PLANS FOR ADDITIONAL INFORMATION.
- 06 REMOVE AND CAP EXISTING DRAIN & WATER LINES.
- 07 REMOVE EXISTING COUNTERTOP AND SINK(S). SEE NEW PLUMBING LOCATIONS ON FLOOR PLAN.
- 08 REMOVE (E) DOOR AND HINGES - JAM AND CASING TO REMAIN.
- 09 REMOVE (E) STAINLESS STEEL COUNTERTOP AND SINK. CAP WASTE AND WATER LINES.
- 10 REMOVE EXISTING RESTROOM TOILETS, URINALS, PARTITION, AND RELATED ACCESSORIES/HARDWARE TO PREP FOR NEW TILE. STORE SAFELY FOR RE-INSTALLATION.
- 11 RELOCATE EXISTING WATER HEATER PER MAINTENANCE & OPERATIONS DIRECTOR.

## LEGEND

- PLYWOOD HAS BEEN REMOVED UP TO 10FT ABOVE FLOOR
- REMOVE PLYWOOD OR DRYWALL @ WALL
- DEMO WALL (FRAMING AND/OR DRYWALL) REFER TO PICTURES
- EXISTING WALL TO REMAIN
- 3/8" IN X-X" OF EXISTING SHEAR (7/16" RATED SHEATHING) SHOWN PER EXISTING STRUCTURAL PLANS
- DEMO AREA - SLAB

REVISIONS / DESCRIPTION	DATE	BY
GENERAL UPDATE PER M&O REVIEW	AUG 11, 2017	SES REC
ADDRRR RELATED DIMS ADA-E	AUG 31, 2017	SES REC
FINAL CONSTRUCTION SUBMITTAL	OCT 01, 2017	SES REC

**COPYRIGHT ROY E COLBERT ARCHITECT 2017**  
ALL RIGHTS RESERVED  
THIS PROJECT RECORD DOCUMENT, DRAWINGS, AND/OR SPECIFICATIONS, HAVE BEEN PREPARED ON THE BASIS OF DATA COMPILED AND FURNISHED BY OTHERS. ROY E. COLBERT ARCHITECT SHALL NOT BE RESPONSIBLE FOR ERRORS AND/OR OMISSIONS RESULTING FROM THAT DATA BEING INCORPORATED INTO THIS DOCUMENT. THESE DRAWINGS AND SPECIFICATIONS, AND THE INCORPORATED IDEAS AND DESIGN, CONSTITUTE AN INSTRUMENT OF PROFESSIONAL SERVICE AND ARE THE SOLE PROPERTY OF ROY E. COLBERT ARCHITECT. THESE DOCUMENTS, IN WHOLE OR IN PART, SHALL NOT BE USED FOR ANY OTHER PROJECT WITHOUT THE DIRECT WRITTEN AUTHORIZATION OF ROY E. COLBERT ARCHITECT.

## ROY E COLBERT ARCHITECTURE PLANNING DESIGN

1997 E. MAIN STREET  
VENTURA, CA 93001  
805 / 650 - 9590 PH  
805 / 650 - 9589 FX  
rcolb@abcglobal.net  
CALIFORNIA C12050  
N.C.A.R.B.



## VENTURA COUNTY COMMUNITY COLLEGE DISTRICT

VENTURA COLLEGE  
4667 Telegraph Road  
Ventura, CA 93003

## DEPARTMENT OF MAINTENANCE & OPERATIONS

4900 Loma Vista Road  
Ventura, CA 93003

## PROJECT DIRECTORY

- ELECTRICAL ENGINEERING:**  
Lucidi & Associates  
3251 Corte Molino #511  
Camarillo, CA 93012  
Ken Lucidi  
(805) 389-6520 x230 Office
- HVAC MECHANICAL / PLUMB ENGINEER:**  
A/E GROUP  
838 East Front Street  
Ventura, CA 93001  
Hugh McTernan  
Phone 805.653.1722
- FIRE PROTECTION ENGINEER:**  
Jack Collings, F.P.E.  
Collings & Associates LLC  
260 Maple Court, Suite 241  
Ventura, CA 93003  
(805) 458-0003  
jcollings@collingsandassociates.com


## VENTURA COLLEGE MAINTENANCE & OPERATIONS INTERIOR TENANT IMPROVEMENT BUILDING C

## DEMOLITION PLAN BUILDING C

SHEET NAME:  
10 JULY 2017  
DATE:  
AS SHOWN  
SCALE:  
C16- 013  
ARCHITECT PROJECT #:  
**A-201**

1-T ACTUAL  
SES  
DRAWN BY:  
P 0107586  
VCCCD PROJECT #:  
SHEET NUMBER: OF SHEETS

# FOR REFERENCE ONLY



**NOTE:**  
WALL BASE TO BE CUT FROM ROLL

**1 FLOOR PLAN - NEW INTERIOR LAYOUT**  
SCALE: 1/4" = 1'-0"

## FLOOR PLAN NOTES

- A. ALL NEW PARTITIONS TO BE METAL STUD FRAMING U.N.O. (ICC-ESR-2374) SEE CONNECTION DETAILS SHEET A-801 FOR MORE INFORMATION.
- B. ALL INTERIOR METAL STUDS MUST BE LISTED BY AN APPROVED TESTING AND LISTING AGENCY (ICC/CBO etc.) AND THEY MUST BE INSTALLED PER THE LISTING AND MANUFACTURERS INSTALLATION INSTRUCTIONS.
- C. PROVIDE BLOCKING AND BACKING AT 2'-0" AFF AND 8'-0" AFF IN INTERIOR PARTITIONS FOR ALL CASEWORK, EQUIPMENT, AND FUTURE ACCESSORIES.
- D. ALL PARTITIONS SHALL BE PAINTED AND RECEIVE 4" VINYL TOPSET BASE UNLESS OTHERWISE NOTED.
- E. FOR ADDITIONAL GENERAL NOTES, LEGENDS, AND SCHEDULES, REFER TO SHEETS A-001 THROUGH A-006
- F. ADA COMPLIANCE: CONTRACTOR TO VERIFY THAT THE EXISTING MULTIPLE STALL RESTROOMS ARE COMPLIANT WITH THE 2016 CBC CHAPTER 11B AND HAVE A DISABLED STALL CLEAR WIDTH AND A 9 INCH TOE SPACE BETWEEN PARTITION WALLS.
- G. AREAS NOT MARKED OR HIGHLIGHTED OR CALLED OUT PER LEGEND ARE NOT IN CONTRACT ON THIS SHEET, TYPICAL.
- H. GC TO PROVIDE DUST PROTECTION THROUGHOUT DEMOLITION AND CONSTRUCTION.
- I. CONTRACTOR TO VERIFY ALL NEW WORK IS COMPLIANT WITH THE 2016 CBC AS ARE ALL RAMPS & HANDRAILS FOR RAMP AND STAIRS AS APPLICABLE TO PROJECT SCOPE.
- J. ALL WORK SHOWN REFLECTS AS-BUILT MEASUREMENTS, HOWEVER, ANY NEW MODIFICATIONS SHALL REQUIRE FIELD VERIFICATION OF ALL DIMENSIONS SHOWN ON THIS PLAN PRIOR TO COMMENCING WORK.
- K. ALL DIMENSIONS ARE TO THE FACE OF METAL STUD UNLESS U.N.O.

## KEY NOTES

- 01 (E) PARTITION WALL PER WALL LEGEND - PROVIDE R-13 FIBERGLASS BATT SOUND INSULATION
- 02 NEW PARTITION WALL TO 10 FEET IN HEIGHT PER WALL SCHEDULE - PROVIDE R-13 FIBERGLASS BATT SOUND INSULATION
- 03 NEW PARTITION WALL TO 7 FEET IN HEIGHT PER WALL SCHEDULE @ SHOWER SEE SHEET A-801 FOR TYPICAL CONNECTION DETAILS.
- 04 ELECTRICAL SUB PANEL BOXES TO REMAIN - SEE ELECTRICAL PLANS FOR ADDITIONAL INFORMATION
- 05 EXISTING LAN (NETWORK) CONDUIT TO REMAIN - SEE ELECTRICAL PLANS FOR ADDITIONAL INFORMATION.
- 06 NEW BUILT-IN CABINETS @ CONFERENCE RM - SEE INTERIOR ELEVATIONS.
- 07 NEW BASE CABINETS & COUNTER TOP - COUNTER TOP TO BE SOLID SURFACE BY DUPONT - CORIAN "LAVA ROCK" PER SPECIFICATIONS - SEE INTERIOR ELEVATIONS
- 08 NEW UPPER WALL CABINETS - SEE INTERIOR ELEVATIONS
- 09 FULL SIZE REFRIGERATOR LOCATION - NEW REFRIGERATOR BY OWNER
- 10 LOCATION FOR IDEA PAINT PRO DRY-ERASE COATING - APPLY PER SPECS, DISCUSS W/ ARCHITECT PRIOR TO APPLICATION FOR DELINEATION OF AREA TO BE COATED.
- 11 METAL SHELVING FOR SAFETY GEAR STORAGE - 48"x16"x7" HEIGHT UNITS. BY OWNER
- 12 CUSTOM FIT SHELVING BY OWNER
- 13 KOHLER TAHOE LAVATORY #K-2890-4U (WHITE) UNDERCOUNTER MOUNT - SEE DETAIL D4/A-802 SEE PLUMBING PLANS
- 14 CHICAGO FAUCET #116.211.AB.1 (ELECTRONIC)
- 15 COUNTER TOP: SOLID SURFACE BY DUPONT - CORIAN "LAVA ROCK" PER SPECIFICATIONS or 3/4" PLYWOOD SEE DETAIL D4/A-802
- 16 LOCKERS BY OWNER
- 17 ELKAY CROSSTOWN 16 GAUGE STAINLESS STEEL 30-3/4" x 18-1/2" x 8". EQUAL DOUBLE BOWL UNDERMOUNT SINK KIT - EFRU3118D8G
- 18 CONFERENCE ROOM 65'-90" NETWORK MONITOR/SMART TV BY OWNER - TO BE WIRED FOR INTERNET AND COMMUNICATION W/ VIDEO CONFERENCE CAPABILITIES. SEE D4/8.01 FOR BACKING DETAILS.
- 19 42"-65" NETWORK CAPABLE MONITOR - INSTALL ON WALL @ 66" HIGH U.N.O. - SEE D4/8.01 FOR BACKING DETAILS.
- 20 VERTICAL FILE CABINETS - 64" TALL - BY OWNER
- 21 UPPER WALL MOUNT ABOVE WORKSTATION HUTCH STORAGE CABINETS BY OWNER.
- 22 28" TALL LATERAL FILE CABINET STORAGE UNITS BY OWNER.
- 23 FIRE ALARM CONTROL BOX TO REMAIN - SEE DEMO PLANS & DETAIL 82/A-801
- 24 Chicago Faucets: DECK MOUNTED 8" FIXED CENTERS HOT & COLD WATER SINK FAUCET - 1100-HA8A85-317AB
- 25 RE-INSTALL EXISTING TOILET, URINAL AND/OR TOILET COMPARTMENT ACCESSORY PER COMPLIANT STANDARDS.
- 26 NEW TOILET COMPARTMENT PARTITIONS: METPAR CORP. THE CORINTHIAN, #FP-500SS STAINLESS STEEL #301/#304 SERIES WITH A #4 SATIN FINISH SEE SPECIFICATION SECTION 10 21 13

## LEGEND

- 8" EXISTING MTL STD WALL
- DARK HATCH DELINEATES FULL HEIGHT
- EXISTING MTL STD WALL - SIZE VARIES
- INDICATES (E) SHEAR PANEL LOCATIONS
- NEW 3 5/8" MTL STD WALL W/ 5/8" GYP BD BOTH SIDES PROVIDE R13 FIBERGLASS BATT SOUND INSULATION
- NEW 4" MTL STD WALL W/ 5/8" GYP BD BOTH SIDES PROVIDE R13 FIBERGLASS BATT SOUND INSULATION
- NEW 6" MTL STD WALL W/ 5/8" GYP BD BOTH SIDES PROVIDE R13 FIBERGLASS BATT SOUND INSULATION
- MICRO-TOPPING RELAY FLOOR FINISH OR ARDEX PREMIUM SELF-LEVELING UNDERLAYMENT - SEE SPEC. 03 35 43
- FLOOR TILE PER WRITTEN SPECIFICATIONS
- HATCHING INDICATES WATERPROOF PAN AREA
- CARPET (PER OWNER); SHAW (TILES), DIRECT GLUE DOWN OR ARDEX PREMIUM SELF-LEVELING UNDERLAYMENT THIS PLAN IS BASED UPON DATA COMPILED AND FURNISHED BY OTHERS

REVISIONS / DESCRIPTION	DATE	BY
GENERAL UPDATE PER JM REVIEW	AUG 11, 2017	SES REC
ADDR RELATED DWGS ADA + IE FINAL CONSTRUCTION SUBMITTAL	AUG 31, 2017	SES REC
▲		
▲		
▲		

**COPYRIGHT ROY E COLBERT ARCHITECT 2017**  
ALL RIGHTS RESERVED  
THIS PROJECT RECORD DOCUMENT, DRAWINGS, AND/OR SPECIFICATIONS HAVE BEEN PREPARED ON THE BASIS OF DATA COMPILED AND FURNISHED BY OTHERS. ROY E. COLBERT ARCHITECT SHALL NOT BE RESPONSIBLE FOR ERRORS AND OR OMISSIONS RESULTING FROM THAT DATA BEING INCORPORATED INTO THIS DOCUMENT. THESE DRAWINGS AND SPECIFICATIONS AND THE INCORPORATED IDEAS AND DESIGNS, CONSTITUTE AN INSTRUMENT OF PROFESSIONAL SERVICE AND ARE THE SOLE PROPERTY OF ROY E. COLBERT ARCHITECT. THESE DOCUMENTS IN WHOLE OR IN PART SHALL NOT BE USED FOR ANY OTHER PROJECT WITHOUT THE DIRECT WRITTEN AUTHORIZATION OF ROY E. COLBERT ARCHITECT.

## ROY E COLBERT

ARCHITECTURE  
PLANNING  
DESIGN

1997 E. MAIN STREET  
VENTURA, CA 93001  
805 / 650 9590 PH  
805 / 650 9589 FX  
rcolb@sboglobal.net  
CALIFORNIA C12050  
N.C.A.R.B.



VENTURA COUNTY  
COMMUNITY COLLEGE  
DISTRICT

VENTURA COLLEGE  
4667 Telegraph Road  
Ventura, CA 93003

DEPARTMENT OF  
MAINTENANCE &  
OPERATIONS  
4900 Loma Vista Road  
Ventura, CA 93003

## PROJECT DIRECTORY

- ELECTRICAL ENGINEERING:**  
Lucci & Associates  
3551 Corte Molisano #511  
Camarillo, CA 93012  
Ken Lucci  
(805) 389-6520 x230 Office
- HVAC MECHANICAL / PLUMB ENGINEER:**  
A/E GROUP  
838 East Front Street  
Ventura, CA 93001  
Hugh McEtemon  
Phone 805.653.1722
- FIRE PROTECTION ENGINEER:**  
Jock Collings, F.P.E.  
Collings & Associates LLC  
240 Maple Court, Suite 241  
Ventura, CA 93003  
(805) 658-0003  
jcollings@collingsandassociates.com

VENTURA COLLEGE  
MAINTENANCE & OPERATIONS  
INTERIOR TENANT IMPROVEMENT  
BUILDING C

## FLOOR PLAN - NEW INTERIORS

SHEET NAME:  
DATE: 10 JULY 2017  
AS SHOWN SES  
SCALE: DRAWN BY:  
C16- 013 P 0107586  
ARCHITECT PROJECT #: VCCDC PROJECT #:  
**A-202**  
SHEET NUMBER: OF SHEETS

1



2



3



4



5





6



7





9



10



11



Name: YTA College  
Inventory: 88841  
by: VENTURA College

12



13





14



15



16



17



18

